

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. R. <u>34</u> E. W.	H 9 & I 8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner H 9: Possibly found the original post, but not its accessories. Point had been perpetuated many years ago by an unknown party with a 1" I.D. x 24" iron pipe; while replacing the monument, two wood post points were found in the swamp bottom, with the 2"x2"x5' upper part of one of them lying preserved in the moss.
Corner I 8: Original post or its accessories not found. Found a 1" I.D. x 24" iron pipe and scribed wood post S45°W 19.4 links, as set probably by Ford Forestry Center personnel for an approximate corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner H 9: Accepted the point of the 2"x2"x5' tamarack post as probably being the original, as it is definitely the older of the two posts found, and was probably not even seen by the party who placed the pipe. This point is 40.01 ch. E'ly of an original section corner. Replaced the tamarack post on 9/15/71 with a new monument described below.
Corner I 8: The found iron pipe appears to have been set at the record compass bearing and distance from the section corner to north. As this section line is about 40 links shorter than the record, the placement of the 1/4 corner at record distance seemed unlikely as being consistent with the evidence on the ground. Therefore, on 12/14/72, re-established the corner on line between Sec. Corners 39, 70 ch. to N & to S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner H 9:
 B. Spruce 6 S54°E (mag.) 22.1 ft. "1/4S, NBT"
 B. Spruce 6 S85°W (mag.) 36.8 ft. "1/4S, NBT"
 Tamarack 5 S14°W (mag.) 32.3 ft. "1/4S, NBT"
Witnesses for Corner I 8:
 Cedar 10 S71°W (mag.) 38.0 ft. "1/4S, NBT"
 Cedar 6 N30°W (mag.) 28.4 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 22, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581