

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

P. ARAGA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. XXX R. 34 XXX W.	K8 & K9
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner K8: Original post or its accessories not found. Found a 1" I. D. x 22" bent iron pipe N83°W .783 ch., probably placed by Ford Forestry Center personnel; the point having been previously witnessed by a J. Pine 7 S10°E 23.9 ft.

Corner K9: Original post or its accessories not found. Found a 3"x3"x4' squared cedar post in place, and many old blazes on trees surrounding it; also fragments of possible older post in the soil.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner K8: Found the short iron pipe to be inconsistent with the Sec. corners N and S of it, and with other corners in the area also; therefore on 6/5/73 re-established the corner on line between existing section corners 39.855 ch. to N and to S.

Corner K9: As the found post is consistent with other original or accepted corners in and around this section, it was accepted as reasonably representing the original corner location and a new monument placed on 9/15/71.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner K8: J. Pine 10 S75°W (mag.) 87.2 ft. "1/4S, NBT"
 J. Pine 9 N69°W (mag.) 75.6 ft. "1/4S, NBT"

Witnesses for Corner K9: Red Maple 12 S39°W (mag.) 29.7 ft. "S26, NBT"
 Cedar 7 N43°E (mag.) 29.6 ft. "S24, NBT"
 Cedar 8 N19°W (mag.) 35.8 ft. "S23, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY *Arthur O. Enger* DATE July 6, 1973
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581