

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 34 E. W.	K 6
2. PROPERTY CONTROLLING IN SECTION 14	T. 49 N. R. 34 E. W.	2, 6, & 7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K6: No evidence of original post or its accessories. Corner had been perpetuated by D. DeLaMater, R.L.S., probably in the early 1950's, as I found a bent DNR 1" I.D. x 48" iron pipe with 4" brass cap pulled out of the road bed in which the corner lies.

Corners 2, 6, & 7: Not established in original survey, nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K6: Monument replaced on 9/15/71 from DeLaMater's NBT's. Corner may have been perpetuated by DeLaMater from monument set previously by Ford Motor Co. personnel. Corner is neither at midpoint nor on line between Sec. Corners to N and S, so possibly is an original.

Corner 2: Established 11/19/71 on line between Sec. Cor. 19.846 ch. E. and 1/4 cor. 19.846 ch. W.

Corner 6: Established 5/15/72 at intersection of quarter-quarter section lines.

Corner 7: Established 12/8/72 on line between Sec. Cor. 19.910 ch. N and 1/4 cor. 19.910 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments at all four corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses to Corner K6: J. Pine 10 N42°W (mag.) 49.2 ft. "NBT"

J. Pine 12 S56°W (mag.) 64.1 ft. "NBT"

Witnesses to Corner 2: J. Pine 9 S34°E (mag.) 46.1 ft. "1/16S, BT"

R. Oak 6 N70°W (mag.) 2.1 ft. "1/16S, BT"

Witnesses to Corner 6: J. Pine 9 N63°W (mag.) 23.7 ft. "1/16S, BT"

J. Pine 6 N69°E (mag.) 17.0 ft. "1/16S, BT"

Witnesses to Corner 7: J. Pine 7 N19°W (mag.) 17.9 ft. "1/16S, BT"

J. Pine 12 S63°W (mag.) 36.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 16, 1973

MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581