

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>34</u> E. R. <u>34</u> W.	J 6
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>49</u> N. <u>34</u> E. R. <u>34</u> W.	5 & 9
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

None of these corners was established in the original survey; subsequently, only Corner J6 was established, and then only by approximation with a 4"x4"x4' squared wood post S84°W 9.6 ft. from true corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner J6:** Established 11/9/71 at intersection of quarter section lines.
- Corner 5:** Established 5/15/72 on line between Center 1/4 cor. 19.981 ch. S and N 1/4 cor. 19.981 ch. N.
- Corner 9:** Established 5/15/72 on line between Center 1/4 cor. 19.846 ch. W and E 1/4 cor. 19.846 ch. E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" alum. cap.
- Witnesses for Corner J6:**
- J. Pine 6 S78½°E (mag.) 10.7 ft. "1/4S, BT"
  - J. Pine 6 N50°E (mag.) 20.7 ft. "1/4S, BT"
  - J. Pine 7 N42°W (mag.) 21.4 ft. "1/4S, BT"
  - J. Pine 5 S26°W (mag.) 20.7 ft. "1/4S, BT"
- Witnesses for Corner 5:**
- J. Pine 6 S47°W (mag.) 24.5 ft. "1/16S, BT"
  - J. Pine 6 S42°E (mag.) 36.4 ft. "1/16S, BT"
- Witnesses for Corner 9:**
- J. Pine 8 N20°W (mag.) 18.2 ft. "1/16S, BT"
  - J. Pine 6 S20°W (mag.) 21.7 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 15, 1973

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581