

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 34 W.	J 7
2. PROPERTY CONTROLLING IN SECTION 14	T. 49 N. R. 34 W.	12
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J7: Original post or its accessories not found. Found a 1" I.D. x 24" iron pipe and a 4" x 4" x 4' squared and scribed wood post in place as set by Ford Forestry Center personnel.

Corner 12: Not established in original survey and only by approximation, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J7: Corner replaced on 11/9/71 as found, on line between Sec. Corners 39.748 ch. to E and to W.

Corner 12: Established 5/15/72 on line between Center 1/4 cor. 19.928 ch. N and S 1/4 cor. 19.928 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner J7: J. Pine 7 N68°W (mag.) 11.4 ft. "1/4S, NBT"
J. Pine 6 N15°E (mag.) 19.5 ft. "1/4S, NBT"

Witnesses for Corner 12: J. Pine 5 N65°E (mag.) 13.1 ft. "1/16S, BT"
J. Pine 6 N54°W (mag.) 2.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 15, 1973

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581