

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. R. <u>34</u> E. W.	H 7, I 6, I 7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners H 7, I 6, and I 7: None of the original posts or accessories was found.
Corner H 7: Found a 4"x4"x4' squared wood post in place as set probably by Ford Forestry Center personnel.
Corner I 6: Found a monument similar to/described for Corner H7.
Corner I 7: Found a 1" I.D. x 40" iron pipe and a 4"x4"x4' squared wood post as set probably by Ford Forestry Center personnel.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H 7: Found post had been set on line between Sec. Corners 39.749 ch. to E and to W. Replaced post on 12/11/72 with monument described below.
Corner I 6: Found post had been set on line between Sec. Corners 39.850 ch. to N and to S. Replaced post on 11/9/71 with monument described below.
Corner I 7: Found post had been set by double proportionate measurement from corners 79.498 ch. W, 79.401 ch. S, 79.496 ch. E, and 79.70 ch. N. Replaced pipe on 11/9/71 with monument described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner H 7: J. Pine 7 S53°W (mag.) 41.3 ft. "1/4S, NBT"
 J. Pine 8 N73°W (mag.) 88.7 ft. "1/4S, NBT"

Witnesses for Corner I 6: J. Pine 6 N65°W (mag.) 11.9 ft. "1/4S, NBT"
 J. Pine 6 S61°E (mag.) 18.8 ft. "1/4S, NBT"

Witnesses for Corner I 7: J. Pine 7 S59°W (mag.) 9.5 ft. "S22, NBT"
 J. Pine 7 N51°W (mag.) 17.6 ft. "S15, NBT"
 J. Pine 6 N42°E (mag.) 11.9 ft. "S14, NBT"
 J. Pine 7 S53°E (mag.) 22.7 ft. "S23, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 22, 1973

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581