

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>34W</u>	<u>C11</u>
	T <u>49N</u> R <u>34W</u>	<u>E11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 05 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11		●	●									
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C11) Corner common to Sections 29-30-31-32. Reestablished in 1959 by Billy D. Buckler RLS, by single proportionate measurement between section corner 2 miles north and section corner 1 mile south. 1" pipe with 4" brass cap. 8" Jack Pine N58E 66 links, 8" Jack Pine S58E 113 links, 6" Jack Pine N70W 85 links.

(E11) Corner common to Sections 28-29-32-33. Corner recovered in 1958 and recorded in 1959 by Billy D. Buckler, RLS. 2" iron pipe with 3" brass cap. 15" Red Pine N26W 39 links, 8" J. Pine S89E 48 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C11) Recovered the 1959 monument as described, a 1" ID iron pipe capped with a 4" dia. brass MI Dept. of Conservation tablet, appropriately stamped, in good condition, and at record bearing from the 1959 witnesses. The J.Pine NW is in good condition with overgrown blazes. The J.Pine NE is a stump. The J.Pine SE is dead and down. Left the monument in place and marked new witnesses as described below.

(E11) Recovered the monument as described in the 1959 recordation, a 2" ID iron pipe capped with a 3" brass tablet, appropriately stamped, in good condition, projecting about 3.6' above ground, and at record bearing and distance from the remains of the 1959 witnesses. The Red Pine is a windthrow and the Jack Pine is only rotting remains. Left the monument in place and marked new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C11) Found 1" pipe with 4" brass cap.

Blazed and scribed the following:

4" J. Pine N23E 13.6' "S29 NBT"

6" J. Pine S61E 20.6' "S32 NBT"

5" J. Pine S45W 8.4' "S31 NBT"

The 1959 witness J. Pine 11" N69W 56.2'

was found with overgrown blazes.

Distances are to notch in lower blaze.

Bearings are magnetic.

(E11) Found 2" pipe with 3" dia. brass

cap. Blazed and scribed:

5" B.Spruce N02W 31.2' "S29 NBT"


5" J.Pine N11E 52.1' "S28 NBT"

4" B.Spruce S78E 102.7' "S33 NBT"

5" J.Pine S42W 38.6' "S32 NBT"

Bearings are magnetic. Distances are to

notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/13/00

For the Michigan Department of Natural Resources - Forest Management Division