

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | | |
|--|---------------------------------------|---------------|-------|
| <u>Baraga</u> <small>(County)</small> | Located In: | Corner Code # | |
| 1. Public Land Survey | T ___ R ___ | _____ | _____ |
| | T ___ R ___ | _____ | _____ |
| | T ___ R ___ | _____ | _____ |
| | T ___ R ___ | _____ | _____ |
| 2. Property Controlling in Section | S <u>32</u> T <u>49N</u> R <u>34W</u> | _____ | 6 |
| 3. Miscellaneous Property in Sec. | S <u>32</u> T <u>49N</u> R <u>34W</u> | _____ | 5 |
| | S ___ T ___ R ___ | _____ | _____ |
| | S ___ T ___ R ___ | _____ | _____ |



4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 31 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 (6-Sec. 32) Northeast 1/16 corner, Section 32. Corner not established in the original survey. Found no subsequent record.
 (5-Sec. 32) North 1/16 corner Section 32. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (6-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. At the position for the corner I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (5-Sec. 32) Established the corner midway and on a straight line between quarter corner 1317.95' north and center of section 1317.95' south. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (6) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
 8" J. Pine N03E 21.2' "1/16S BT"
 5" J. Pine S53E 9.9' do
 9" J. Pine S45W 20.0' do
 8" J. Pine S78W 17.8' do
 Placed squared J. Pine post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
 (5) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
 6" J. Pine S52E 28.3' "1/16S BT"
 11" J. Pine S08E 42.1' do
 9" J. Pine S41W 22.5' do
 4" J. Pine N81W 32.8' do
 Placed squared J. Pine post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 4/12/00
 Surveyor's Michigan License No. 33986