

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>49N</u> R <u>34W</u> | <u>D1</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Feb 01 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (D1) Quarter corner common to Sections 5 T49N-R34W and 32 T50N-R34W. Remonumented in the original position by Billy D. Buckler, RLS, in 1950. 1" Pipe with 4" brass cap. 12" J.Pine S28W 28 links, 10" J.Pine N14W 15 links, 8" J.Pine S55E 18 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D1) Recovered the 1950 monument, a 1" ID iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, in good condition and at record bearing and distance from the stump remains of the three 1950 NBTs. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D1) Found 1 ID iron pipe with 4" brass cap. Blazed and scribed:
 11" W.Pine North 10.1' "1/4S NBT"
 8" W.Pine N81E 21.3' do
 10" R.Pine S12W 7.7' do
 15" W.Pine N55W 31.2' do
 Set sq'd W.Pine post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/2/01

For the Michigan Department of Natural Resources - Forest Management Division