

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga  
(County)

Located In:

Corner Code #

- |                                    |  |            |
|------------------------------------|--|------------|
| 1. Public Land Survey              | T <u>49</u> R <u>34</u> N              | <u>87</u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 03 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(87) Quarter corner common to Sections 18-19. Reestablished by the method of proportionate measurement in 1959 by Billy D. Buckler RLS. 1" Pipe with 4" Brass cap. 5" J. Pine N83E 27 links, 5" J. Pine S05E 10 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(87) Recovered the 1959 monument as described, in good condition, and at record bearing and distance from the 1959 NBTs. The J.Pine NE is in good condition. The J.Pine SE is a 2' high stub with notch and scribing visible.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(87) Found 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:  
 7" J.Pine S65E 4.3' "1/4S NBT"  
 7" Hemlock S66W 48.4' do  
 5" J.Pine N82W 30.0' do  
 6" J.Pine East 18.1' do  
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/15/01

For the Michigan Department of Natural Resources - Forest Management Division