

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 34W	C6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/11/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17 and 18. 1959 - Billy D. Buckler RLS reestablished the corner midway and on line between two Section corners. No evidence of original corner. Set 1" pipe with 4" brass cap. 8" J.Pine S14E 73.5 links, 9" J.Pine N24W 63 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) The 1959 monument and accessories were not recovered and appear to have been destroyed by logging activity. Reestablished the corner midway and on the Section line between Section corners 2640.82' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" J.Pine N71E 21.4' mrkd "1/4S NBT"
 5" J.Pine S33W 31.25' do
 5" J.Pine N68W 9.0' do
 5" J.Pine N16W 23.65' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/24/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division