

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 33W	G9
	T _____ R _____	(GCDB 400300)
	T 49N R 33W	H9
2. Property Controlling in Section	S _____ T _____ R _____	(GCDB 440300)
	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/21/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1852 - Established by Z.B.Searles, Deputy. Set post. Y.Birch 12" S57°E 37 links, Y.Birch 10" N74°W 12 links. 1944 - N.T.Thompson RLS states that he found the Y.Birch BT S57°E "OK. Stub" and that the Y.Birch BT NW was "gone". Set Cedar post in pile of rocks. New BTs: Y.Birch 7" N17°W 19.5', Y.Birch 14" N63°E 30.9', Sugar 6" S54°W 12.5'.

(H9) Quarter corner common to Sections 22 and 27. 1852 - Established by Z.B.Searles RLS, midway and on the Section line between Section corners 40.07 chains east and west. Set post. Fir 8" S39°E 33 links, Ironwood 8" N26°W 33 links. 1944 - N.T.Thompson RLS states that the BTs are gone and that he set a spruce post in rocks with new BTs: Sugar 8" N5°W 6.00', Sugar 9" S37°E 11.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) The original post was not recovered. Found a 1-3/8" dia. Axle in a rock mound, at record bearing and distance from the remains of the original BT Y.Birch S57°E, now very rotten, and at record bearing and distance from the 1944 NBTs. The Y.Birch N63°E in good condition, the Y.Birch N17°W a cut stump, and the Sugar S54°W, a cut stump. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(H9) The original post and accessories were not recovered. Found a 3/4" ID I.pipe, projecting 12" a.g., in a rock mound, at record bearing and distance from the 1944 accessories, now both stumps. The NBT Sugar S37°E is very rotten, the NBT Sugar N05°W is a recently-cut stump. Accepted the pipe as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Found 1-3/8" dia. axle in a mound of rock. Set measuring nail with MDNR tag in the side of:
 15" Y.Birch N67°E 30.95' old blazes (1944 NBT)
 12" Maple N06°E 45.9' mrkd "S22 NBT"
 10" Y.Birch S21°E 32.9' "S27 NBT"
 8" Sugar S52°W 13.05' "S28 NBT"
 Set sq'd cedar post adjacent.
 E= 7890600.168 N= 205316.420

(H9) Found 3/4" ID I.pipe in a mound of rock. Set measuring nail with MDNR tag in the side of:
 9" Sugar N36°W 14.15' mrkd "1/4S NBT"
 4" Sugar N23°E 8.25' do
 6" Sugar S55°E 16.6' do
 11" Sugar S77°W 19.7' do
 E= 7891398.307 N= 205304.081

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
 Coord. Ref.=NGS PID RL0476: N= 196482.411 m. E= 7879234.516 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/27/2015

For the Michigan Department of Natural Resources, Forest Resources Division

