

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 33W	G10
	T _____ R _____	(GCDB 400240)
2. Property Controlling in Section	T 49N R 33W	I9
	S _____ T _____ R _____	(GCDB (500300))
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/20/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27 and 28. 1852 - Established by Zelotes B. Searles, Deputy. Set post midway and on the Section line between Section corners 39.99 chains north and south. Fir 10" S48°E 34 links, Sugar 10" N31°E 41 links. 1944 - Norman T. Thompson RLS, reestablished the corner according to creek call [given in the original notes as "Brook 2 C SE" 24 links south of the corner]. Set cedar post Elm 9" S13°E 20.8'; Sugar 3" S79°W 5.5'.

(I9) Corner common to Sections 22-23-26-27. 1852 - Established by Zelotes B. Searles, Deputy. Set post. Sugar 8" S54°W 21 links; Y.Birch 16" N45°E 32 links. 1944 - N.T.Thompson RLS found the Sugar BT "OK, down" and the Y.Birch BT "standing but rotten". Set cedar post in pile of rocks. Hemlock 8" N51°W 25.7'; Sugar 3" N13°E 16.8'. 1979 - Robert Schmeling RLS recovered and remonumented the 1944 position. Set 1"ID I.pipe with 4" alum. Mead Corp. cap. New BTs: Sugar 7.8" S40°E 38.2'; Sugar 6.4" S66°W 36.1' (rec. L1 P338).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) The original post and accessories were not recovered. Found a 1"ID iron pipe with rotted post lying adjacent, at record bearing and distance from the 1944 Elm NBT, now a rotted stump. The 1944 Sugar NBT was not recovered. A Ford Motor Co. location tag on a 21" Y.Birch (used as NBT this date), earliest date inscribed Jan. 20 1952, faces the pipe. Accepted the position of the pipe as a careful and faithful reestablishment of the position of the original corner.

(I9) Found the 1979 monument as described, in good condition, and at record bearing and distance from the remains of the 1944 NBTs. The Sugar is down and rotted, the Hemlock is a standing dead stub. The 1979 NBTs were also recovered, at substantial record bearing and distance. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Found 1"ID I.pipe projecting 1.6' a.g. Set measuring nail with MDNR tag in the side of:
 21" Y.Birch N53°W 7.05' mrkd "1/4S NBT"
 6" Sugar N60°E 19.5' do
 4" Spruce S58°E 11.4' do
 9" Sugar South 6.2' do
 E= 7890583.942 N= 204513.576

(I9) Found 1"ID I.pipe with 4" Mead Corp. Cap. Set measuring nail with MDNR tag in the side of:
 7" Sugar S68°W 35.9' old scribing (1979 NBT)
 5" Sugar N42°W 11.4' mrkd "S22 NBT"
 4" Maple N68°E 20.4' "S23 NBT"
 7" Maple S38°E 13.45' "S26 NBT"
 A sq'd cedar post found adjacent.
 E= 7892203.255 N= 205278.676

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum
 Coord. Ref.=NGS PID RL0476: N= 196482.411 m. E= 7879234.516 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/27/2015

For the Michigan Department of Natural Resources, Forest Resources Division

