

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>33W</u>	<u>H11</u>
	T <u>49N</u> R <u>33W</u>	<u>J13</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Party Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Oct 24 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(H11) Quarter corner common to Sections 27 and 34. 1852 - Established by Zelotes Searles, Deputy Surveyor: [East] Corrected between Sections 27 and 34 ...40.18 Set quarter section post. Fir 10 S76E 26 links, Fir 10 N67W 3 links. ...80.36 Section corner". Dec. 8, 1941 - Notes of N.T.Thompson RLS found at Northern Hardwoods office at Bovine, MI state: "New B.T. B.Cherry 12 N41E [?] 6'1", Elm 9 S2E 10'7"."

(J13) Quarter corner common to Section 35 T49N-R33W and Section 2 T48N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor: "West on South side of Section 35 ...40.00 Set Cedar post quarter section corner. Cedar 12 N18E 46 links, Cedar 8 N18W 34 links. ... 80.00 Set Sugar post corner of Sections 34-35". July 16, 1941 - Notes of N.T.Thompson RLS found at Northern Hardwoods office in Bovine, MI state: "Run from E. cor W. V.0 [deg] hit 106 ft. N. of W. cor. Ch back E set 1/4 at 2640. cont. US.41 = 3600 ft and E. cor No B.T. but 20 ft short. Corr. V.1 degree 10'E. Corr = 2635 ft or 5270 ft." Cedar BTs for J13 are noted as "gone" and "New BT W.Pine 5 N18E 6', W.Pine 4 S42W 5'9"."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H11) The original post and accessories were not recovered. Found a 1" ID iron pipe at record bearing and distance from the 1941 NBT Cherry, now a 10" dead stub with Ford Motor location poster affixed and "BT" plainly scribed on lower blaze, and at record bearing and distance from probable Elm NBT, now dead and down. The pipe is located N51E 15.2' from the record GLO position (midway and on line between Section corners). I accept the pipe as the best available evidence of the position of the original corner.

(J13) The original post and accessories were not recovered. Found a 1 3/8" ID iron pipe projecting 2 ft and set firm in a small mound of rock at record bearing and distance from the 1941 W.Pine NBT N18E 6 ft, in good condition. Given the reference to US41 (old US41) crossing the township line 3600' east of K13 and the division of the 20' excess, I conclude that Mr. Thompson reestablished this corner by proportionate measurement over the two miles between I13 and M13. The pipe was recovered S02W 9.7' from that position and it is 2634.6' east of I13. I accept the pipe as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H11) Found 1" ID Iron pipe. Set measuring nails in:  
 12" Cedar S76E 34.4' mrkd "1/4S NBT"  
 10" Y.Birch S23E 32.7' do  
 5" Sugar S31W 25.15' do  
 9" Sugar N04W 4.35' do  
 Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.

(J13) Found a 1 3/8" ID iron pipe. Set measuring nails in:  
 15" W. Pine N20E 6.85' mrkd "1/4S NBT"\*  
 7" Cedar East 16.3' do  
 10" Cedar S11E 36.1' do  
 8" W.Pine S66W 9.4' do  
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. \* denotes 1941 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/29/06

For the Michigan Department of Natural Resources, Office of Land and Facilities