

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>33W</u>	<u>H12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>49N</u> R <u>33W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Oct 20 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H12) Center of Section 34. Not established in the original survey.
 (5-Sec. 34) North 1/16 corner, Section 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
 (5-Sec. 34) Established the corner midway and on a straight line between Quarter corner 1321.89' north and Center of Section 1321.89' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Spruce N17W 20.1' mrkd "C1/4 BT" 12" Cedar N52E 53.8' do 6" Spruce S11E 20.1' do 14" Cedar S48W 50.7' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Spruce N24E 23.8' mrkd "1/16S BT" 7" Cedar S72E 42.4' do 8" Cedar S68W 34.3' do 16" Cedar N53W 25.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/29/06