

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 34 T 49N R 33W	14
	S 34 T 49N R 33W	13
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Oct 20 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (14-Sec. 34) South 1/16 corner between Sections 34 and 35. Not established in the original survey.
- (13-Sec. 34) Southeast 1/16 corner, Section 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (14-Sec. 34) Established the corner midway and on line between Quarter corner 1291.73' north and Section corner 1291.73' south.
- (13-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (14) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
12" Y.Birch N60E 39.2' mrkd "1/16S BT"
10" Sugar S03W 13.2' do
7" Sugar N53W 17.7' do
6" Sugar North 10.2' do
Set sq'd cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag. | (13) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
10" Spruce S54E 18.2' mrkd "SE1/16 BT"
4" Sugar S37E 10.1' do
4" Sugar S25W 6.1' do
4" Sugar N71W 14.5' do
Set sq'd cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/29/06

For the Michigan Department of Natural Resources, Office of Land and Facilities