

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N.R. 32 W


Baraga COUNTY

DESCRIPTION OF CORNER West 1/8 Corner between Sections 7 and 18

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 8/17/61

WITNESSES TO CORNER....8" Soft Maple (BT) S 30° W 19 Links



10" Soft Maple (BT) N 70° W 39 Links

3/4" Iron Pipe West 03 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by single proportionate measure from Section Corner to West and 1/4 Corner to East.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE August 18, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler