

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 32W C-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 583 - 584.

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	6	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T50N, R32W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

See back of form.

[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R32W.

Found a 1½" dia. iron pipe projecting 24" above ground in agreement with the local new bearing trees as recorded by the BLM and listed in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R32W.

See back of form.



Signed by *[Signature]*

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T50N, R32W.

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Sugar 18 S25°E 22 lks. (Gone)

and a

Hemlock 16 S54°W 49 lks.

(Recovered as ground level stump remains approximately 26" in dia.)

This corner was recovered by Michael Avery and Stephen Douglas of the Bureau of Land Management during the course of a survey conducted from 17 September 1982 to 30 September 1983 and approved 8 July 1985. According to the field notes of this survey, a 1½" dia. iron pipe projecting 24" above ground was found in agreement with the remains of both U.S. bearing trees. The BLM did not remonument the corner nor record any new bearing trees. However the following local new bearing trees were noted by the BLM:

Sugar Maple 13 S61°E 11½ lks.

(Presently alive and 15" in dia. having a partially healed mid-trunk blaze.)

Hemlock 10 S18°W 21 lks.

(Presently alive and 11" in dia. having a healed mid-trunk blaze.

Set 60d spike W/side S20°W 13.86')

Maple 12 N18°W 14 lks.

(Found a sugar maple presently alive and 13" in dia. having partially healed upper and mid-trunk blazes.

Set 60d spike W/side N22°W 9.24')

C. Description of monument for corner and accessories established to perpetuate location the position of the corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R32W.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	N/side	9" Sugar Maple	N67°E	25.04'
Set 60d spike	E/side	14" Basswood	S27°E	13.35'
Set 60d spike	SE/side	10" Hemlock	S57°W	23.20'
Set 60d spike	S/side	11" Red Maple	N67°W	30.92'

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".