

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 32W E-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ R _____
- in Section S _____ R _____
- 3. Miscellaneous S _____ R _____
- Property in Section S _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
585 - 586.

Nelda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of _____ the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Closing Corner common to Sections 4 and 5, T50N, R32W.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1; Closing Corner common to Sections 4 and 5, T50N, R32W.

Reestablished corner on line at proportionate distance between the south one-quarter corner of Section 35, T51N, R32W and the southeast corner of Section 35, T51N, R32W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1; Closing Corner common to Sections 4 and 5, T50N, R32W.

See back of form.



Signed by *[Signature]*

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Closing Corner common to Sections 4 and 5, T50N, R32W.

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Sugar Maple 16 S49°W 32 lks. (Gone)

and a

Yellow Birch 12 S44°E 41 lks. (Gone)

This corner was considered to be lost during the course of a survey conducted by Michael Avery and Stephen Douglas of the Bureau of Land Management from 17 September 1982 to 30 September 1983 and approved 8 July 1985. The BLM did not remonument the corner.

The late Norman Thompson, RLS #4348 states in his field notes, date not indicated (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he "found 2" iron pipe, no B.T."

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1; Closing Corner common to Sections 4 and 5, T50N, R32W.

Set a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	8" Sugar Maple	N10°E	43.98'
Set 60d spike	N/side	11" Sugar Maple	S77°E	22.09'
Set 60d spike	W/side	14" Sugar Maple	S08°E	22.30'
Set 60d spike	NW/side	14" Sugar Maple	S27°W	32.51'
		2" Iron Pipe	N65°E	48.70'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".