

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>32W</u>	<u>I-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 31ST
DAY OF DECEMBER A.D. 1997 AT
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
815

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
10-9-97
[Signature]

I, Michael Mileski, in a field survey on 11 December, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1; Closing Corner common to Sections 2 and 3, T50N, R32W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with an elm post witnessed by a Black Ash 6 S30°W 42 lks. and a Sugar 10 S34°E 53 lks.

This corner was considered lost and reestablished on line at the proportionate distance between the S¼ corner of section 31, T51N, R31W and the S¼ corner of section 32, T51N, R31W by Norman Thompson, P.S. #4348 on 2 December 1941. Mr. Thompson monumented the corner with an iron pipe and noted the following new bearing tree: Black Ash 10 S60°E 12.3'

Copies of Mr. Thompson's field notes were obtained from the Northern Hardwoods' office in L'Anse.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R32W;

Found a 2" diameter iron pipe projecting 21" above ground as set by Mr. Thompson. From the single-proportioned position for this corner, Mr. Thompson's monument is located S74°E a distance of 5.8 feet. With all due respect to Mr. Thompson, I remonumented this corner at the single-proportioned position as determined from our measurements.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R32W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 12" above ground.

Set 7" spike	E/side	7" Yellow Birch	N10°E	15.35'
Set 7" spike	S/side	8" Yellow Birch	N89°E	34.02'
Set 7" spike	NE/side	6" Yellow Birch	S37°E	9.56'
Set 7" spike	SE/side	6" Yellow Birch	S21°W	13.88'
Set 7" spike	N/side	12" Hemlock	N70°W	53.48'
		1" dia. iron pipe	S74°E	5.8'
		6" Steel fence post w/ yellow sign	North	1.5'



All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

Signed by [Signature]
Surveyor's Michigan License No. 39091

LIBER 4 PAGE 815 23 Dec 1997