

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
587 - 588.

- 1. Public Land Survey T 50N R 32W K-1
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Section S T R

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | |
| 3 | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | |
| 5 | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | |
| 7 | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | |
| 9 | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | |
| 11 | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | |
| 13 | | | | | | | | | | | |

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-1; Closing Corner common to Sections 1 and 2, T50N, R32W.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R32W.

Found a 1½" iron pipe in agreement with Mr. Thompson's new bearing tree the condition of which is described in Part A. This monument is 270 feet (U.S. = 289.74 feet) west of the thread of a 5 foot wide creek. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R32W.

See back of form.



Signed by Michael Mileski

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

K-1; Closing Corner common to Sections 1 and 2, T50N, R32W.

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monument with a hemlock post witnessed by a

Hemlock 8 S21°W 21 lks.

and a

Sugar Maple 8 S62°E 25 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes possibly taken in 1941 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he recovered the hemlock U.S. bearing tree as an "old stump, no marks". Mr. Thompson does not indicate what type of monument he set, but did note the following new bearing tree:

Hemlock 12 S23°E 21.0'

(Presently alive and 20" in dia. having a healed mid-trunk blaze.

Set 60d spike W/side S25°E 21.00')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R32W.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

| | | | | |
|---------------|---------|---------------|-------|--------|
| Set 60d spike | E/side | 11" Hemlock | N22°E | 20.06' |
| Set 60d spike | S/side | 22" Hemlock | S77°E | 25.90' |
| Set 60d spike | NW/side | 16" Hemlock | S36°W | 45.40' |
| Set 60d spike | NE/side | 10" Red Maple | N58°W | 42.15' |

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".