

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BABAGA COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 33 W.	A10, C10
2. PROPERTY CONTROLLING IN SECTION	T. S. R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner A10: Original monument and accessories not found. Found old blaced lines in area.
- Corner C10: Original monument and accessories not found. Found old 2" iron by unknown length which has been used as corner for many years.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner A10: Restored 12-15-81 at old approximate corner location. Fits good at midway on line between corners north and south.
- Corner C10: Restored 12-17-81 at 2" iron. Fits good with corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner A10: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 8" Hemlock N62E 6.0 ft. 1/4S,NBT
 - 6" Hemlock S04W 3.8 ft. 1/4S,NBT
 - 12" Hemlock N26W 28.9 ft. 1/4S,NBT
- Corner C10: 2" iron 2 ft. out of ground.
 - 14" Hemlock S72E 8.2 ft. 1/4S,NBT
 - 6" Maple N83W 12.8 ft. 1/4S,NBT
 - 10" Sugar N23E 33.6 ft. 1/4S,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-82
CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith Sackett
 Michigan Dept. of Natural Resources

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006