

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 33 W.	A9, All
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 3, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner A9:** Original monument and accessories not found. Found old blazed lines N-S-E-W. Also found 1½" I.D. iron pipe N11 E 27.4 ft.
 - Corner All:** Original monument and accessories not found. Found old blazes and post in area.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner A9:** Restored at blazed line intersection. Fits good with other corners.
 - Corner All:** Restored at old post and blazes. Fits good with other corners.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner A9:** Set 1" I.D.x32" Iron Pipe with 4" alum. cap.
 7" Maple N53W 23.8 ft. S24,NBT
 8" Maple S60E 14.2 ft. S30,NBT
 1½" I.D. Pipe N11E 27.4 ft.
 - Corner All:** Set 1" I.D.x32" iron pipe with 4" alum. cap.
 14" Hemlock S39E 19.2 ft. S31,NBT
 7" Sugar N81W 7.9 ft. S25,NBT
 6" Sugar N05E 5.2 ft. S30,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-82
CHIEF OF SURVEY PARTY
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

