

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. S. R. 33 E. W.	B9, C9, C11
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-8- 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law.

A. Description of original monument and accessories and/or subsequent restoration:

- Corner B9: Original monument and accessories not found.
- Corner C9: Original monument and accessories not found. Found 3/4" I.D. by unknown length I.P. set by Ford Motor Co. Surveyor.
- Corner C11: Original monument and accessories not found. Found 3/4" I.D. by unknown length Iron Pipe set by Ford Motor Co. Surveyor.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner B9: Restored midway and on line between section corners east and west.
- Corner C9: Restored at Iron Pipe. Position fits with other corners in area.
- Corner C11: Restored at Iron Pipe. Position fits with other corners in area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| Corner B9: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.
5" Birch N5E 20.1 ft. 1/4S, NBT
5" Maple S53E 21.7 ft. 1/4S, NBT
4" Maple S73W 19.1 ft. 1/4S, NBT | Corner C11: 3/4" I.D. by unknown length Iron Pipe.
14" Cedar S15 W 6.5 ft. S31, NBT
8" Cedar S85E 34.3 ft. S32, NBT
10" Cedar N68E 26.5 ft. S29, NBT |
|--|---|
- Corner C9: 3/4" I.D. by unknown length Iron Pipe.
 14" Sugar N27W 5.0 ft. S19, NBT
 8" Sugar S56E 9.7 ft. S29, NBT
 6" Sugar S43W 14.5 ft. S30, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-16-83

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Department of Natural Resources

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006