

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 33W	A8
	T 50N R 33W	A6
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on A8 05/23/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (A8) Quarter corner common to Section 19 T50N-R33W and Section 24 T50N-R34W. 1846 - Established by Austin Burt Deputy Surveyor midway and on the Range line between Section corners 40.00 chains north and south. Set Sugar post. Y.Birch 18" S74W 56 links, Y.Birch 18" N78E 14 links. Found no subsequent record.

(A6) Quarter corner common to Section 18 T50N-R33W and Section 13 T50N-R34W. 1846 - Established by Austin Burt Deputy Surveyor midway and on the Range line between Section corners 40.00 chains north and south. Set Cedar post. Y.Birch 10" S10E 32 links, Y.Birch 8" N66W 16 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (A8) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the Range line between Section corners 2624.42' north and south, proportionate to the original record.

(A6) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Range line between Section corners 2624.42' north and south, proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (A8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Sugar S57E 27.3' mrkd "1/4S NBT"
 5" Sugar S50W 35.2' do
 10" Maple N87W 24.8' do
 6" Sugar N52W 30.2' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.
 (A6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 17" Hemlock S68E 4.7' mrkd "1/4S NBT"
 10" Hemlock S15E 15.4' do
 4" Y.Birch S78W 2.6' do
 10" Y.Birch N30W 2.3' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 10/24/2011
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Management Division

