

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 21 T 50N R 33W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat	_____	
5. Private Claims	_____	

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 08/02/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 21) West 1/16 corner between Sections 16 and 21. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 21) Established the corner midway and on the Section line between Section corner 1316.29' west and Quarter corner 1316.29' east. From the position thus established, the extension of an old line of occupation to the north is 4.5' east. Said line consists of two 3.5" dia. iron posts with evidence of old fence line. Long-time occupant of the SW1/4 of the SW1/4 of Sec. 16, Mr. Ralph Sayotovich, born in 1915, says the fence had stood there for 90 years and had been recently removed. The monumented position is approx. 6 ft. north of the center of the paved surface of Golf Course Rd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 5/8"x24" rebar with plastic MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 Power Pole 503316L32 N66E 31.8'
 Power Pole 503316L20 S69W 75.65'
 Power Pole 503316L30 N76W 87.3'
 A metal sign post "Golf Course Rd 15623"
 bears N59W 42.0' distant.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/24/2011
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Management Division