

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 33W G-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 589 - 590.

Theda J. Sobillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Michael Mileski, in a field survey on December, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1; Closing Corner common to Sections 3 and 4, T50N, R33W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

See back of form.

[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1; Closing Corner common to Sections 3 and 4, T50N, R33W.

Found a 2½" aluminum pipe with 3" brass cap in agreement with both of the BLM new bearing trees. The monument is located on the edge of a ridge and lies 160 feet (U.S. = 159.72') west of a creek. This monument is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1; Closing Corner common to Sections 3 and 4, T50N, R33W.

See back of form.



Signed by *Michael Mileski*

Date 28 December 1995

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

G-1; Closing Corner common to Sections 3 and 4, T50N, R33W.

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Cedar 10 S47°E 5 lks. (Gone)

and a

Cedar 5 S33°W 6 lks. (Gone)

This corner was reestablished at proportionate distance by Stephen Douglas of the Bureau of Land Management during the course of a survey conducted from 13 May 1987 to 4 November 1987 and approved 24 March 1989. Mr. Douglas monumented the corner with a 2½" aluminum pipe with 3" brass cap appropriately stamped as to location and noted the following new bearing trees:

Maple 5 S10°E 17½ lks.

and a

Maple 7 S70°W 21½ lks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1; Closing Corner common to Sections 3 and 4, T50N, R33W.

Left existing monument in place adding "PA 345 1995" to the brass cap.

Set 60d spike	E/side	7" Red Maple	N34°E	27.09'
Set 60d spike	W/side	5" Red Maple	S10°E	11.55'
(BLM NBT, added upper face blaze.)				
Set 60d spike	SE/side	10" Red Maple	S58°W	28.67'
Set 60d spike	SE/side	8" Red Maple	S68°W	14.19'
(BLM NBT, added upper face blaze.)				
Set 60d spike	NE/side	8" Red Maple	N37°W	20.95'

The above three non-BLM new bearing trees are marked with upper and lower face blazes and scribed "NBT".