

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>33W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 31ST
DAY OF DECEMBER A.D. 1997 AT
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
813-814

Helda Bishop
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 29 July, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1; Closing Corner common to Sections 2 and 3, T50N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R33W;

Found a 2½" diameter aluminum pipe with a 3" brass cap projecting 6" above ground as set by the BLM in 1987. The position of this monument was verified by a traverse. I did not remonument the corner, but stamped "PA 345 1997" to the cap. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R33W;

Found a 2½" aluminum pipe with a 3" brass cap stamped as to location projecting 6" above ground.

Set 7" spike	SE/side	8" White Birch	N53°E	35.31'
Set 7" spike	SW/side	7" Red Maple	S68°E	29.94'
Set 7" spike	NE/side	6" Sugar Maple	S89°W	19.80'
Set 7" spike	SW/side	7" Red Maple	N37°W	19.15'
		6" Steel fence post w/ yellow sign	North	1.5'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-9-97
[Signature]



LIBER 4 PAGE 813

Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 23 Dec 1997

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

I-1; Closing Corner common to Sections 2 and 3, T50N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Fir 8 S87°E 21 lks.

and a

Cedar 10 S55°W 47 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 13 May 1987 to 4 November 1987 and approved on 24 March 1989, this corner was considered lost and reestablished on line at the proportionate distance between the S $\frac{1}{4}$ corner of section 31, T51N, R32W and the SE corner of section 31, T51N, R32W. The BLM monumented this position with a 2 $\frac{1}{2}$ " x 30" aluminum pipe with brass cap and noted the following accessories:

Sugar Maple 6 S27°E 80 lks. (52.80')
Presently alive and 7" in diameter having a partially healed lower blaze with scribing visible.

Set 7" spike NE/side Measured S25°E 52.85'

White Birch 7 S45°W 12 lks. (7.92')

Presently alive and 9" in diameter having a healed lower blaze.

Set 7" spike SE/side Measured S48°W 7.92'

To each of the above BLM new bearing trees, I added an upper blaze. Both blazes and a band around the tree at the upper blaze were painted red.