

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 33W K-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
591 - 592.

Hilda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Michael Mileski, in a field survey on December, 1995,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1; Closing Corner common to Sections 1 and 2, T50N, R33W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R33W.

Found Mr. Douglas' monument as described in Part A to be in reasonable agreement
with its intended position. Accepted as a careful and faithful reestablishment of the
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R33W.

See back of form.



Signed by Michael Mileski

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

K-1; Closing Corner common to Sections 1 and 2, T50N, R33W.

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a pine post witnessed by a

Yellow Pine 9 S75°E 15 lks. (Gone)

and a

Yellow Pine 10 S11°W 26 lks. (Gone)

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 13 May 1987 to 4 November 1987 and approved 24 March 1989 this corner was considered lost and monumented with a 2½" dia. aluminum pipe with 3" brass cap appropriately stamped as to location. This monument was reset in 1994 by Mr. Douglas also at a proportioned position in order to remain harmonious with the recovered original south one-quarter corner of Section 32, T51N, R32W (Refer to LCR for this corner recorded Liber 4 pages 539-540).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1; Closing corner common to Sections 1 and 2, T50N, R33W.

Left existing monument in place adding "PA 345 1995" to the brass cap.

Set 60d spike	N/side	12" Red Pine	N55°E	4.40'
Set 60d spike	SW/side	10" Red Pine	S34°E	5.19'
Set 60d spike	SE/side	6" Red Pine	S60°W	8.55'
Set 60d spike	W/side	12" Red Pine	N03°W	17.29'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".