

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 33W K-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 563 - 564.

Melda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2; One-quarter Corner common to Sections 1 and 2, T50N, R33W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

See back of form.

Mileski

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2; One-quarter Corner common to Sections 1 and 2, T50N, R33W.

Found a 2-1/2" dia. aluminum pipe with a 3" brass cap appropriately stamped as to location in agreement with Mr. Thompson's ties to both U.S. bearing trees the condition of each as described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2; One-quarter Corner common to Sections 1 and 2, T50N, R33W.

See back of form.



Signed by Michael Mileski

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

K-2; One-quarter Corner common to Sections 1 and 2, T50N, R33W.

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a maple post witnessed by a

Yellow Pine 12 S24°E 22 lks.

(Recovered as a knocked over petrified 36" tall stump with the lower half of the lower face blaze evident with no remaining marks.)

and a

White Pine 12 N42°W 41 lks.

(Recovered as ground level stump remains.)

The late Norman Thompson, RLS #4348 states in his field notes possibly taken in 1943 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he recovered the southeast U.S. bearing tree as an "old stub, burnt notch" and the northwest U.S. bearing tree as an "old stub, direction ok, distance short 2½', set cedar post". Mr. Thompson did not note any new bearing trees.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 13 May 1987 to 4 November 1987 and approved 24 March 1989 this corner was recovered and remonumented with a 2½" dia. aluminum pipe with 3" brass cap appropriately stamped as to location. The BLM established the following new bearing trees:

Red Pine 15 S75°E 51½ lks.

and a

Red Pine 11 N18°W 12 lks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2; One-quarter Corner common to Sections 1 and 2, T50N, R33W.

Left existing monument in place adding "PA 345 1995" to the brass cap.

Set 60d spike	W/side	5" Red Pine	N15°E	11.70'
---------------	--------	-------------	-------	--------

Set 60d spike	N/side	20" Red Pine	S66°E	64.02'
---------------	--------	--------------	-------	--------

(BLM NBT, added upper face blaze.)

Set 60d spike	E/side	10" Red Pine	S15°E	16.50'
---------------	--------	--------------	-------	--------

Set 60d spike	S/side	10" Red Pine	S70°W	29.37'
---------------	--------	--------------	-------	--------

(BLM NBT, added upper face blaze.)

The above two non-BLM new bearing trees are marked with upper and lower face blazes and scribed "NBT".