

44.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga
(County)

Located In: _____ Corner Code CB

1. Public Land Survey T 50N R 34W _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S 20 T 50N R 34W _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on August 09, 1995, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	10	9	8	7	6	5	4	3	2	1			
7													
8	13	12	11	10	9	8	7	6	5	4	3	2	1
9													
10	16	15	14	13	12	11	10	9	8	7	6	5	4
11													
12	19	18	17	16	15	14	13	12	11	10	9	8	7
13													

A. Description of original monument and accessories and/or subsequent restoration:

(CB) Quarter corner common to Sections 19-20. Original corner established by Wm. Burt, 1849 as follows: "Set maple Qr. Section post... Hemlock 12 S67E 24, Hemlock 14 N31W 7". Found no subsequent record.
(WC South of E8) Witness corner to an Original Line Tree located on the south 1/2 mile of the line between Sections 20-21. Line between 20-21 established in 1849 by William Burt: "North between Sections 20 & 21... 26.31 Y Pine 10, ... 40.00 Set Hemlock Qr Section Post..." The line tree was recovered by A.O. Enger, RLS in 1974. Original notches visible. The notched portion was removed in 1974 and is on display at the Michigan Dept. of Natural Resources District 1 Headquarters in Baraga. Enger used this tree to reestablish the Quarter Corner common to Sections 20-21.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(CB) Found no evidence of original post or accessories. Searched for and did not find any trace of the Hemlock line trees between Sections 19-20 noted in the original notes. Found no evidence of the position of the original corner on the ground. Reestablished the corner on a straight line between Section corners 2629.66 ft. north and south. At the position for the corner I placed a 1"IDx32" iron pipe, projecting about 9", capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
(WC South of E8) Found the stump remains of the Y. Pine Line Tree, 25.2426 ch. north of the monumented section corner 20-21-28-29, and 14.0464 ch. south of the monumented quarter corner. The line tree was found 2.6 ft. west of a straight line between these corners and I accepted it as being a monument to the location of the true section line. The tree had been burned several times, plainly revealing the original notches. At a point 1.50' north of the center of the tree, and on a straight line between the center and the quarter corner to the north, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet stamped "T50N R34W WC 20/21 LINE TREE 1.5' SOUTH 8-9-95 PS 33986". The corner falls on a steep SW slope down to Kelly Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(CB) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:
12" W. Pine N15W 32.1' "1/4S NBT"
12" Maple N52E 37.3' "1/4S NBT"
12" Db1. Hemlock S44E 27.1' "1/4S NBT"
12" Maple S37W 38.2' "1/4S NBT"
Bearings are magnetic.

(WC line tree) Set a 1" pipe with a 4" MDNR cap. Blazed and scribed the following bearing trees:
8" Maple S46E 14.2' "WC BT"
14" R. Pine S62W 8.3' "WC BT"
24" R. Pine N43W 10.4' "WC BT"
26" R. Pine N21E 31.5' "WC BT"
Bearings are magnetic, Distances horizontal.



Signed by Stephan J. Szyszkoski Date 9-6-95
Surveyor's Michigan License No. 33986