

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

(County)

Located in:

Corner Code ##

1. Public Land Survey	T	<u>50N</u>	R	<u>34W</u>	<u>C9</u>	
	T	<u>50N</u>	R	<u>34W</u>	<u>C7</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on August 09, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9		●											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C9) Corner common to Sections 19-20-29-30. Corner re-monumented in 1961 by Billy D. Buckler, RLS from Original BT. 1" pipe with 4" brass cap. 12" Red Oak S01W 120 links, 9" Twin Red Oak N45W 120 links. Squared and scribed 7" Soft Maple at corner.
 (C7) Corner common to Sections 17-18-19-20. Corner re-monumented in 1961 by Billy D. Buckler, RLS from adjacent corners, line calls, and possible BT stump mound. Buckler placed a 1" pipe with 4" brass cap and marked the following, 17" Red Pine S40W 36 links, 6" Soft Maple N01W 59 links, 5" Soft Maple S57E 52 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) Found and accepted Buckler's monument as described, in good condition, at record bearing and distance from is 1961 Oak witnesses, both in good condition. The Soft Maple adjacent to the corner was cut to facilitate GPS observations in 1995. Left the monument in place and marked two new bearing trees as described below. The Original W. Pine BT, noted in the 1961 record N65E 25 links, is still evident. No markings are visible.

(C7) Found and accepted Buckler's monument, in good condition, at record bearing (corrected for declination change) and distance from his remaining witness, the Red Pine, found 24" dia. with old blazes, in good condition. the Maples are now both gone. Left the monument in place and marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Found 1" iron pipe with 4" Brass cap. Blazed and scribed the following new bearing trees:
 4" Maple S33E 23.2' "S29 NBT"
 12" Maple N04E 17.4' "S20 NBT"
 Bearings are magnetic.

(C7) Found 1" pipe with 4" brass cap. Blazed and scribed the following new bearing trees:
 6" Maple S77W 24.6' "S19 NBT"
 3" Oak N38E 46.7' "S17 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 9-6-95
 Surveyor's Michigan License No. 33986