

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N.R. 34-35W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 7-18-12-13

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5-31-61 with R. Hinds and D. St. Ours

WITNESSES TO CORNER..... 12" Soft Maple (S12 NBT) N5°W 34 links



9" Soft Maple (S18 NBT) S77°E 34 links

9" Y. Birch (S13 NBT) S17°W 57½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Y. Birch B.T. down and in poor condition bearing N32°W 13 links. Found two wood posts in place with numerous blazes at Corner. Position checks well to good Corner ½ mile East.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE December 28, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler