

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N.R. 34-35W

Benaga COUNTY


DESCRIPTION OF CORNER 1/4 Corner between Sections 19-24

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5-16-61 with Duane St. Ours

WITNESSES TO CORNER..... 10" Cedar (1/2 S NLT) N82°W 39 1/2 links

9" Soft maple (1/2 S NLT) N62°E 35 links



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Hemlock B.T. bearing N20°W 10 links. Tree down and in very poor condition. Found blazes and scars in rotted wood. Found 16" Cedar 8 links SW of Corner with numerous names and dates. Found no evidence of Cedar B.T., probably destroyed by old logging road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 28, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler