

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50N N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19-20-29-30

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-17-61 with Duane St. Ours.

WITNESSES TO CORNER..... 12" Red Oak (S30 NBT) S 1°W 120 links



9" Twin Red Oak (S19 NBT) N45°W 120 links

Squared and scribed 7" Soft Maple at Corner

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one W. Pine B.T. bearing N65°E 25 links. Stump is badly burred. Found bottom of upper face with axe marks and overgrowth. Found Hemlock line tree 29.32 chains East of Corner. Record distance = 29.40 chains. Found two Pine stumps in proper position to West of corner. These are probable line trees.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 27, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler