

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 29 28  
32 33

CORNER MONUMENT 1" Iron pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-18-61

WITNESSES TO CORNER..... 6" Tamarack(S32 NBT) S 17°W 11 Links



6" Spruce (S29 NBT) N 87°W 15½ links

5" Soft Maple (S33 NBT) S 81°E 43½ links

AND 7" Oak (S28 NBT) N51°E 40 links

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was re-established by W. Pine turn out which may be B.T. (w. pine 18" S28°E 29 links). Found face on 32" stump facing corner. Swamp edges to south and west are good for distance. Distances to section corners to North and South check well.

**SURVEYOR'S SEAL**

SIGNED Billy E. Buckler DATE December 27, 1961  
REGISTERED LAND SURVEYOR  
Billy E. Buckler