

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 17-18-19-20

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-18-61 with H. Hinds

WITNESSES TO CORNER..... 17" Red Pine (S19 NBT) S40° 36 links



6" Soft Maple(S18 NBT) N 1° 59 links

5" Soft Maple(S20 NBT) S57°E 52 links

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was replaced from one Y.Pine stump bearing S61°W 16 links. Stump is marked as approximate Corner by Ford Motor Co. men. Position fits well with Section Corner 1 mile South; 4 Corner 2 mile North and stream to East. Found mound N65°E 21 links for possible Hemlock B.T. Corner lies on South side of road squared and scribed 8" aspen at Corner.

**SURVEYOR'S SEAL**

SIGNED Billy D. Buckler DATE December 27, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler