

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections $\frac{20}{29}$

CORNER MONUMENT 1" Iron pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-18-61

WITNESSES TO CORNER..... 6" Soft Maple (1/4 S NBT) S80°W 19 links



7" W. Birch (1/4 S NBT) S81°E 35 links

8" Soft maple (1/4 S N.T) N37°W 12 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed the proportionate distance between section corner to East and line tree to west and in line with same. No original evidence.

SURVEYOR'S SEAL

SIGNED Billy J. Buckler DATE December 27, 1961
REGISTERED LAND SURVEYOR
Billy J. Buckler