

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N. R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 Corner between sections 32-33

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-18-61 with R. Hinds

WITNESSES TO CORNER..... 12" Red Pine (1/4 S NBT) S 60°W 92 links



9" W. Pine (" ") S 10°E 26 links

8" W. Pine (" ") N 37°E 15 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two original W. Pine B.T.'s bearing S60°W 28 links. (has been cut leaving lower half of bottom blaze and notch) N30°E 10 links found stump bottom, badly rotted.

No evidence of use.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 27, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler