

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N. R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 26-27-34-35

CORNER MONUMENT 1" Pipe with Brass Cap

DATE MONUMENT PLACED AND WITNESSED 6-1-61 with R. Hinds and D. St. Ours

WITNESSES TO CORNER..... 11" Soft Maple (S34 NBT) S57°W 70 links



13" Hard Maple (S27 NBT) N11°W 91½ links

7" Twin Hard Maple (S35 NBT) S46°E 41½ links

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was replaced from **Two** Original B.T.'s Y. Birch bearing S10°E 09 links. Stump has been cut, center has rotted away. Soft Maple bearing N32°W 23 links, Tree dead but standing, both faces rotted out. Found 1" Iron Pipe 23½ links North of Corner. Corner lies in island formed by Junction of roads to South, East and Northwest. Corner found by Leroy Stevens, D.F.

**SURVEYOR'S SEAL**

SIGNED Billy D. Buckler DATE December 28, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler