

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 27-28-33-34

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6-1-61

WITNESSES TO CORNER..... 9" Soft Maple (S34 NBT) S66°E 42½ links



14" Soft Maple (S33 NBT) S18°W 79 links

16" Hemlock (S28 NBT) N85°W 75 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Hemlock Stp. bottom bearing N22°W 20 links.  
Found old down squared Hemlock at Corner Distance 3.47 chains East to pond checks  
with Field Notes. North edge of Marsh 6.50 chains west checks with original notes.  
Found numerous very old blazes both East and West of Corner.  
Corner lies 4½ chains east of road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 28, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler