

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 22-23-26-27

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 6-1-61

WITNESSES TO CORNER..... 14" Soft Maple (S27 NBT) S68°W 32½ links



11" Soft Maple (S26 NBT) S63°E 45 links

9" Y. Birch (S23 NBT) N64°E 61 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Hemlock BT bearing N60°W 06 links, a stub in excellent condition. Most scribe marks in evidence.
Found Y. Birch B.T. bearing S54°E 09 links down and in poor condition.
Found Iron Fence post in Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 28, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler