

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N.R. 34 W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 7-18

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/10/65 with Forester Stevens

WITNESSES TO CORNER..... 6" H. Maple (1/4S NBT), N 02° W, 07 lks.



10" H. Maple (1/4S NBT), S 31° E, 43 1/2 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two Original BT's. Both Cedar down. (Cedar 12" N 28° E, 16 lks.) has scribe marks on upper face. (Cedar 12" S 42° W, 20 lks.) is rotted, but checks for bearing and distance.

SURVEYOR'S SEAL

SIGNED Frank J. Bray
Frank J. Bray
REGISTERED LAND SURVEYOR DATE 2/11/1965