

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 50 N. 8. R. 34 K. W.	L-3, K-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 6, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
Corner L-3: Original monument and accessories not found. Found 5" cedar with Ford Motor Co. location poster - N40W - 35.6'. Found old cedar with blaze facing corner - N19E - 5.4'. Numerous other blazes in area.

Corner K-3: Original monument and accessories not found. Found old post and Ford Motor Co. location poster approximately two chains SW. This post does not fit with any other evidence in area.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
Corner L-3: Re-established corner at intersection of old blazes.

Corner K-3: Re-established by land calls north, south, east and west and also section corner north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Corner L-3: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

- 6" Cedar S 1° W 34.1' ¼S NBT
- 7" Cedar N72° W 33.7' ¼S NBT
- 4" Cedar S41E 17.8' ¼S NBT

Corner K-3: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.

- 9" Cedar S60E 11.1' S12 NBT
- 4" Cedar N 2E 11.3' S 1 NBT
- 7" Cedar S45W 21.0' S11 NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-10-77  
CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

