

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 50 N. 34 E. W.	K-2
2. PROPERTY CONTROLLING IN SECTION _____	1, T. 50 N. 34 E. W.	8
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-2: Original monument and accessories not found. Numerous blazes in area. Good east-west blazed line.

Corner 8: Not set on original survey nor subsequently apparently. Found old fence one chain north. George Wadaga, lifelong resident, put fence up many years ago and claims to have put it north of actual line.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-2: Re-established 4/7/77 on line between corners north and south.

Corner 8: Established 4/8/77 on subdivision of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-2: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.

7" maple	S69°E	7.7'	1/4 S NBT
4" maple	S45°W	5.5'	1/4 S NBT
7" maple	N10°E	8.2'	1/4 S NBT

Corner 8: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.

6" maple	N 5°W	16.3'	1/16 S BT
7" maple	S68°E	27.7'	1/16 S BT
8" maple	S 6°W	45.9'	1/16 S BT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET