

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>50</u> N. <u>34</u> E. <u>34</u> W.	<u>I2 & K1</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I2: 1/4 corner between Sec. 2 & 3, T50N, R34W:
 Hemlock post (Not found. See B for subsequent monument.)
 Y. Birch 12 N36E 12 (Not found. No subsequent accessories found.)
 Fir 7 S28W 29 (Not found. No subsequent accessories found.)

Corner K1: Closing Cor. on 5th Corr. Line between Sec. 1 & 2, T50N, R34W:
 Cedar post (Not found. No subsequent monuments found.)
 Y. Birch 12 S32½W 21 (Not found. No subsequent accessories found.)
 Hemlock 8 S26E 36 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I2: Re-established 5/7/76 proportionately on line between Sec. Cor. 40.117 ch. S and 34.259 ch. N. Found a recent squared spruce post S46½°E 31.3 feet for an approx. corner. Corner is 20.06 ch. S of a stream 3 lks. wide c SE, on section line according to original notes, the record distance being 20.15 ch.

Corner K1: Re-established 4/23/76 proportionately on line between standard corners on 5th Correction Line, 7.853 ch. E and 154.423 ch. W. Corner falls approx. in construction centerline of old E & W township road and in line with old field edge and fence S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 6 S60°W (mag.) 11.8 ft. "1/4S, NBT"
 Red Maple 6 N12°E (mag.) 6.0 ft. "1/4S, NBT"

Corner K1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 5 N41°W (mag.) 19.0 ft. "S32, NBT"
 Hemlock 5 S35°W (mag.) 37.0 ft. "S 2, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE October 9, 1976
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

