

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>5</u> , R. <u>34</u> W.	E3 & G3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E3: Sec. Corner 4, 5, 8, & 9, T50N, R34W:
 Sugar post (Not found. See "B" for possible subsequent monument.)
 Sugar 12 N28E 31 (" " No subsequent accessories found.)
 Sugar 12 S30W 40 (" " No subsequent accessories found.)

Corner G3: Sec. Corner 3, 4, 9, & 10, T50N, R34W:
 White Birch post (Not found. See "B" for subsequent monument)
 W. Pine 12 S32E 71 (" " No subsequent accessories found.)
 W. Pine 5 N20W 34 (" " No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E3: Re-established 8/29/74 at intersection of construction centerlines of county road going E and old township roads going N and S, and in line with old fence going W. When digging hole for a monument, found a remnant wood post and piece of crock, which may have been old corner monuments, though found no record of same.

Corner G3: On 4/10/73, re-witnessed an iron pipe found in centerline intersection of E & W and N & S roads, set by unknown party, but possibly by a former local surveyor named Schwalm. Corner bears S0°29.5'E 73.996 ch. (record: 73.84) from closing corner N; N0°22.2'W 79.665 ch. (record: 80.00) from corner S; S89°53.7'W 78.507 ch. (record: 79.46) from corner E; and S89°49.4'E 79.966 ch. (record: 79.75) from Corner W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E3: 1" I.D. x 24" iron pipe with 3½" aluminum cap, buried in road.
 Twin Butternut 8 & 14 S37°W (mag.) 34.55 ft.
 Power Pole N13½°W (mag.) 104.35 ft.
 Note: Distances are to nail with 3/4" brass washer stamped "WITNESS MARK".

Corner G3: Iron pipe (size and length unknown), buried in road.
 J. Pine 14 N31°E (mag.) 68.02 ft.)
 R. Pine 16 S87°E (mag.) 71.45 ft.) Distances to nail in object.
 Power Pole S40°W (mag.) 41.72 ft.)
 Concrete marker S30°E (mag.) 68.6 ft. (from center)

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE October 20, 1976
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

