

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>34</u> E. <u>W.</u> R. _____	C5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 31, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Sec. Corner 7, 8, 17, & 18, T50N, R34W:

Yellow Birch post	(Not found. No subsequent monuments found.)
Hemlock 10 N50W 9	(" " " " accessories found.)
Hemlock 10 S38E 39	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner re-established on true line between original 1/4 cor. S0°30.4'E 40.303 ch. and sec. cor. N0°30.4'W 79.892 ch. and at a point bearing N89°36.1'E 38.150 ch. from an original 1/4 cor. to W and S89°36.1'W 79.694 ch. from sec. cor. to E. Found the E-W direction to be consistent with the direction of N89°31.3'E measured between original corners 1/2 mile and 1 mile W. Having retraced some 26 miles of section lines in this twp., I have found that direction between corners is a more reliable guide to missing corner locations than are distances, and particularly the N & S directions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
Sugar Maple 7 S40°W (mag.) 22.6 ft. "S18, NBT"  
Sugar Maple 7 N77½°W (mag.) 22.4 ft. "S7, NBT"

**Note:** As some of the survey control points were destroyed by construction activities subsequent to measurement of the lines and prior to corner re-establishment, the monument as placed may vary slightly from its intended calculated position, but is believed to be within a foot of that position.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE October 20, 1976  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

