

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>34</u> E. <u>W.</u>	<u>C3 & F5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C3: Sec. Corner 5, 6, 7, & 8, T50N, R34W:

Cedar post	(Not found. No subsequent monuments found.)
Hemlock 12 S22W 51	(" " " " accessories found.)
Y. Birch 20 N20E 42	(" " " " accessories found.)

Corner F5: 1/4 Corner between Sec. 9 & 16, T50N, R34W:

Maple post	(Not found. See "B" for subsequent monument.)
Y. Pine 18 S9E 22	(Found. No subsequent accessories found.)
Y. Pine 18 N7E 34	(" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C3: Re-established 4/23/76 in construction centerline of an E & W county road, presumed to be the section line by common report, and in line with an old fence going N. Position bears S89°51'W 80.256 ch. (Record: 80.40) from a corner to E and N0°30.4'W 79.892 ch. (Record: 80.00) from a corner to S. Found a 2" iron pipe on edge of road at end of the fence line, 23.59 ft. N of corner reported here, presumably a witness of some sort.

Corner F5: On 8/29/74 placed a new monument at record bearing and distance from original BT to SE, identified from axe notch and trace of overgrowth. Found a stump corresponding to the second BT at proper bearing, but at 37 lks. rather than the recorded 34 lks. Unknown party has placed a 1 3/4" iron pipe N73°33.5'W 2.048 ch. from this corner, apparently unaware of the original BT mentioned herein.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C3: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap, buried in road.
 Cedar 14 N60°E (mag.) 84.6 ft. "S5, NBT"
 Cedar 11 S38°W (mag.) 110.1 ft. "S7, NBT"

Corner F5: 1" I.D. x 40" iron pipe with 3 1/2" aluminum cap.
 Red Maple 4 N84°E (mag.) 29.3 ft. "1/4S, NBT"
 Red Maple 3 N19°W (mag.) 33.8 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 20, 1976

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

