

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>50</u> N. <u>34</u> E. <u>W.</u>	G5
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Sept. 12, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Sec. Corner 9, 10, 15, & 16, T50N, R34W:

Maple post	(Not found. See "B" for subsequent monument.)
Y. Pine 18 S50E 37	(Not found. No subsequent accessories found.)
Y. Pine 20 N47W 30	(Not found. " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner re-established at intersection of the extensions of true lines from an original 1/4 corner 39.862 ch. S through a White Pine 15 line tree stump 26.299 ch. S and from an original 1/4 cor. 40.463 ch. W through a Y. Pine 16 line tree stump 21.598 ch. W. This appears to me to best satisfy the original field notes as to original corner establishment, as my experience in this twp., based on some 26 miles of retracement lines, shows that proportionate measurements do not fit the actual positions of known original points. Found a twin 10" and 20" red pine S85°W 35.0 feet which has been used for an approximate corner by local foresters. Past logging operations in the corner vicinity have destroyed any possible direct evidence of the corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Red Pine 14 S84°W (mag.) 14.1 ft. "S16, NBT"
 Red Pine 10 S73°E (mag.) 12.4 ft. "S15, NBT"
 Red Pine 15 N6½°W (mag.) 35.1 ft. "S 9, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

